



City of Beatrice, Nebraska

400 ELLA STREET – BEATRICE, NE 68310
PHONE (402) 228-5200 – FAX (402) 228-2312

TOBIAS J. TEMPELMEYER
CITY ADMINISTRATOR
400 ELLA STREET
(402) 228-5211

GREGORY A. BUTCHER
CITY ATTORNEY
400 ELLA STREET
(402) 228-5211

LYLE HARRIS
BUILDING INSPECTOR
205 NORTH 4TH STREET
(402) 228-5250

LINDA S. KOCH
CITY CLERK/
ASST. TREASURER
400 ELLA STREET
(402) 228-5200

JAMES A. BURROUGHS
CITY ENGINEER
205 NORTH 4TH STREET
(402) 228-5208

BRIAN D. DAAKE
FIRE CHIEF
310 ELLA STREET
(402) 228-5246

JASON MOORE
INTERIM LANDFILL
SUPERINTENDENT
400 ELLA STREET
(402) 223-2267

LAUREN RIEDESEL
LIBRARY DIRECTOR
100 NORTH 16TH STREET
(402) 223-3584

BRUCE E. LANG
CHIEF OF POLICE
201 NORTH 5TH STREET
(402) 223-4080

MARK PETHOUD
DIRECTOR OF
PUBLIC PROPERTIES
800 DOANE STREET
(402) 228-5248

July 23, 2014

RE: Curb and Gutter Replacement Project – 2014
5th Street - East Curb from Ella to High Street
9th Street - East Curb from Vacated Nicholls to Tait Street
9th Street - West Curb from Vacated Nicholls to Green Street

To Whom It May Concern:

The City of Beatrice has entered into an agreement with Trauernicht Construction, Inc. for the removal and replacement of curb and gutter along the street sections listed above. The anticipated start date has been established as July 28, 2014 beginning at 5th Street and then proceeding to 9th Street. Each section is expected to take approximately two (2) weeks to complete.

Regarding the 5th Street improvements, barricades will be placed around the work zone temporarily closing the on street parking. Both lanes of traffic along 5th Street will remain open. Due to construction taking place on both sides, 9th Street will be closed to thru traffic.

We realize that there are residents residing along the 9th Street corridor which require vehicular access to their homes at all times. In order to accommodate this situation, their driveway approaches will be done a half at a time. Residents can expect to see the following construction phasing:

1. Saw cut the existing pavement to the limits of removal.
2. Remove the existing curb and gutter along with the drive approaches.
3. Place temporary rock surfacing at the drives to allow vehicular access.
4. Construct the new curb and gutter along with half of the driveway approaches. The other half to remain rock for access.
5. Once the new concrete can be driven on, the first half will be opened for use and the second half of the driveway will be poured.
6. Once the second half of the driveway can be driven on, the entire driveway will be opened for use.

If there are any extenuating circumstances that are in conflict with this operation, please let me know ASAP. Every effort will be made to expedite the project as much as possible.

If you have any questions, comments, or concerns, please feel free to call me at (402) 228-5208, or e-mail me at jburroughs@beatrice.ne.gov.

Sincerely,

James Burroughs, P.E.
City Engineer

Beatrice
NEBRASKA
FOODS TO CALL HOME

www.beatrice.ne.gov